

Training - Practicing Commissioning



PRACOM-EN-P



Face-to-face only



4 days

This course provides practical knowhow so as to get the participants directly confront the reality of the field

Level

Knowledge

Public

Operating and technical staff in charge of commissioning and start-up operations on field

Objectives

Attendees will be able to implement the following skills:

- Anticipate the risks while commissioning and start-up operations
- Identify the key points of the most current operations
- Proceed to main pre-commissioning and commissioning activities

Pedagogical & technical resources

- Experience sharing through applications and cases studies on Oil & Gas units
- Cases studies on the precommissioning, commissioning and start-up of units
- Analysis of incidents occurred while precommissioning, commissioning or start-up phases

Assessment of achievements

- Trainees are assessed throughout the training through practical application phases and interactions with the trainer
- A final on-the-spot evaluation may also be carried out at the end of the course and/or at the end of each module using tests designed to verify the learners' understanding and assimilation of the knowledge linked to the training objectives

Prerequisites

No prerequisites are necessary to follow this course

Responsible

IFP Training instructors, with expertise in the field and trained in modern teaching methods adapted to the specific needs of learners from the professional world

Program

COMMISSIONING & START-UP PHASES IN PROJECT CYCLE

0.5 day

End precommissioning, mechanical completion, commissioning, ready for start-up, start-up permit, performance test runs, temporary and final acceptance.

Commissioning and start-up: a non-linear schedule. SIMOPS. Input data and reference documentation. Punch lists. Management of Change (MOC).

SPECIFIC RISKS TO COMMISSIONING & START UP

0.5 day

Fluid behavior and energy associated hazards. Chemical and physical hazards. Flammability.

Main risks induced by equipment, such as rotating, pressure vessels, thermal or naked flame equipment.
Risks related to utilities start-up: inert gas, nitrogen, steam, instrument air, water, fuel gas, diesel.
Risks evolution from construction to start-up. Transient phases. Safety reviews. Managing leaks.

WHAT TO DO BEFORE COMMISSIONING PROCESS UNITS

1.5 days

End of construction: visual control and checks for static and rotating equipment (no energy, no fluid). Cold clamping. Check of installation standards for piping and instrumentation.
Precommissioning activities: hydraulic tests and process equipment cleaning.
Mechanical completion.
Particular case of Utilities facilities: pre-commissioning, commissioning and start-up (ready for operations).

COMMISSIONING OF PROCESS UNITS & START UP

1.5 days

Chemical cleaning, flushing and blowing. Equipment drying and dynamic testing.
Particular case of instrumentation - Loops and DCS tests. Synchronization.
Preparation for the start-up of rotating equipment.
Prestart-up checks before oil-in. Plant line-up and test run.
Start-up: leak tests, air removal, oil-in. Heating up and hot bolting.
Update of documentation.

To French entities : IFP Training is referenced to DataDock ; you may contact your OPCO about potential funding.
Please contact our disabled persons referent to check the accessibility of this training program : referent.handicap@ifptraining.com